

# Three Unit Product Ready for Delivery



# Three Unit Product Under Construction

Issued and Pending Patents #7,621,967



Fig. 1 Steel Frame with Tine Ports



Fig. 2 Steel Frame with Stud Support



Fig. 2a ¾ Inch Plywood Decking for Floor



Fig. 3 Linoleum Covered Floor



Fig. 4. Three Walls On Floor



Fig. 4a Divider Walls Installed



Fig. 5 ADA Stall with Urinals



Fig. 6. Woman's Stall



Fig. 7 Shower Stall



Fig. 8 ADA Unit With Auto Flushing Urinals



Fig. 9 Ladies Unit With Vanity



Fig. 10 Shower/Toilet Combo Stall



Fig. 11 Front View of Progress on 3 Stall Bldg.



Fig. 12 Women's Unit Middle Stall

Three Unit Lavatory Building With ADA Unisex - Women's and Shower Unit

Patents Issued and Pending



Fig. 13 Shower Stall/Lavatory Combo



Fig. 14 Front Building Finished With Doors Closed



Fig. 15 ADA Unit Completed

**Toilets.com, Inc.**

Phone: 1-800-521-6310

Fax: 1-586-731-0670

E-mail: [info@toilets.com](mailto:info@toilets.com)

Web Site: [www.toilets.com](http://www.toilets.com)

## Figure. 1 Steel Frame with Tine Ports

The steel tine ports are the full length of the frame for increased mobility.  
Frame is 13' x 7.5' and weighs approximately 840 pounds.  
Frame is painted with a plastic base paint.

## Figure. 2. Steel Frame With Treated Floor Wood

### Figure. 2a. Wood Floor

The treated ¾" exterior plywood floor is bolted to the frame and 2" x 4" boards.

## Figure. 3. Linoleum Covered Floor

The wood floor is covered with linoleum. The floor must set for 24 hours before the side walls can be put in place.

## Figure. 4. The outer walls are put in place.

The extrusions and outer walls are put in place and must set for 24 hours.

## Figure. 4a. The divider walls are put in place.

The extrusions and inner walls are put in place and must set for 24 hours.

## Figure. 5. The Inner Walls and ADA Unit Fixtures are Installed.

The ADA Sink and Two Urinals are installed (one lowered for small children).  
The patented toilet bowl and cistern are installed.

## Figure. 6. Ladies Stall

The ladies stall is fitted with a vanity and patented toilet system.

## Figure. 7. The third stall is fitted with a vanity, shower and patented toilet and cistern.

The shower unit is fitted with an inline hot water heater.

## Figure. 8. ADA Unit With Two Urinals

The urinals have been fitted with auto flushing mechanisms easier for child care.

## Figure. 9. Progress on Ladies Lavatory With Vanity

## Figure. 10. Progress on Combination Shower and Toilet Stall

## Figure. 11. Progress on Three Stall Building Front View.

The unit will weigh approximately 1,600 pounds upon completion

### Toilets.com, Inc.

Phone: 1-800-521-6310

Fax: 1-586-731-0670

E-mail: [info@toilets.com](mailto:info@toilets.com)

Web Site: [www.toilets.com](http://www.toilets.com)

## Figure. 12. Women's Middle Stall Completed

The middle section on this unit is a women's unit with vanity.

## Figure. 13. Shower Stall and Lavatory Combination

The third unit is unisex hot water shower with lavatory and vanity.

## Figure. 14. The Three Stall Unit With Closed Doors

The three stall unit contains one ADA compliant stall, one women's stall and one combination shower and lavatory stall.

## Figure. 15. The Unisex ADA Compliant Stall With Two Urinals

This ADA compliant unit has two urinals, one for children and one for adults.

### Toilets.com, Inc.

Phone: 1-800-521-6310

Fax: 1-586-731-0670

E-mail: [info@toilets.com](mailto:info@toilets.com)

Web Site: [www.toilets.com](http://www.toilets.com)